

Main North Road and Kesters Road Intersection Upgrade

Signalisation and upgrade of Intersection

Client Parafield Airport Limited

Location Parafield, SA

Contract Value \$5.22 Million

Completion Date November 2015

Project Description



- Excavate and remove 6,000m³ of earthworks
- Supply and placement of 13,000T of deep lift asphalt
- Supply and installation of 64 new road lighting poles and corresponding trenching, conduits, luminaries, cabling and switchboards
- Supply and installation of stormwater infrastructure including 375mm and 1800mm RCP and 31 precast pits
- Signalisation of intersection including lanterns, signal control box and 22 loop detectors

Bardavcol Pty Ltd

7 Churchill Road North, Dry Creek SA 5094
 Tel: +61 8 8260 5044 Fax: +61 8 8349 6715
 marketing@bardavcol.com.au
 www.bardavcol.com.au