

# Pimba to Roxby Downs Shoulder Sealing

*180kms of shoulder sealing*

<b>Client</b>	Department for Planning, Transport & Infrastructure
<b>Location</b>	Pimba to Roxby Downs
<b>Contract Value</b>	\$4.5 million
<b>Completion Date</b>	August 2012

## Project Description

As part of the early works package for the expansion of the Olympic Dam uranium mine. Bardavcol has been contracted to widen the section of road between Roxby Downs and Pimba in anticipation of the very wide load haulage needed to service the proposed expansion project.

The project consists of 178km of shoulder widening to create dual 3.5 metre wide traffic lanes.

Key Elements of the project include;

- Import and spreading 50,000 tonne of rubble
- Bomag treatment and compaction of 2.5m wide strip
- 7mm primer seal followed by a 14-7mm final seal placed 1.2m wide.
- Line marking following completion



### Bardavcol Pty Ltd

7 Churchill Road North, Dry Creek SA 5094  
 Tel: +61 8 8260 5044 Fax: +61 8 8349 6715  
 marketing@bardavcol.com.au  
 www.bardavcol.com.au

**BARDAVCOL**  
*Proudly South Australian*