

Sturt Highway Upgrade Stages 1–5

21.5km of Roadway between Gawler and Nuriootpa

Client Department for Planning, Transport & Infrastructure

Location Gawler to Nuriootpa

Contract Value \$95 million

Completion Date June 2010

Project Description



- Comprises of 5 stages of works incorporating the duplication of 21.5km of roadway between Gawler and Nuriootpa, a truck rest area and on/off ramp upgrades to Greenock, Seppeltsfield and Nuriootpa.
- Included the placement of over 400,000m³ of earthworks and 270,000t of asphalt.
- Blasting of 18,000m³ of rock including pre split of batter to allow for development of on/off ramps.
- Incorporated three bridges and one steel arch culvert over Greenock Creek.
- Considerable design changes implemented throughout all stages without additional cost to the client or delays to the completion.
- Constructed on a major highway under difficult traffic control conditions.

Bardavcol Pty Ltd

7 Churchill Road North, Dry Creek SA 5094
Tel: +61 8 8260 5044 Fax: +61 8 8349 6715
marketing@bardavcol.com.au
www.bardavcol.com.au

BARDAVCOL
Proudly South Australian